

6175 NW 167th Street – Unit G13 Miami Lakes, FL 33015 305-362-4320 Office / 305-362-4502 Fax www.precisionventilation.com

"Manufacturer's Representatives of Air Moving Equipment"

Revised E-QUOTATION #1

Date: 6/26/2020

Contact / Co / Ph: Jose Antonio Galavis /InTeg - Integral Engineering / 305-907-0262

Email: jgalavis@integca.com

Job: FPL BUILDING E Boca Raton

Conditions & Comments:

- Prices Subject To Sales Taxes & Quote Valid For A Period Of 60 Days From The Above Date
- Full Freight Allowed To South Florida Via Standard Transit Time
- VFD's, Starters, Controls, Sensors, Firestats, T'Stat's, End Switches Not Included Unless Otherwise Stated Below
- Additional Fees Will Apply For Lift Gate Service, Prior Delivery Appointment, Residential Delivery
- Additional Fees Will Apply For Export If Furnigated Wood & Certified Stamp Is Required
- We Accept Visa, Master Card, Discover and American Express Credit Cards Plus 3% For Bank Fee

OPTION #1:

Tuttle & Bailey Air Distribution consisting of:

- (27) pcs of 24 x 24 Lay-In to Round Necks, Model A1100 Plaque Supply Diffuser with Insulated Blanket, White
- (02) pcs of 12 x 12 Lay-In to Round Necks, Model A1100 Plaque Supply Diffuser, White
- (27) pcs of 24 x 24 to 22 x 22 Square Necks, Model A70D Louvered Fixed Blades Ceiling Return Grille, White
- (06) pcs of 24 x 24 to 19 x 19 Model A70DFB Louvered Fixed Blades Ceiling Return Grille with Filter Frame, White
- (04) pcs of 8 x 8 Model CRE500, Egg-crate Return Grille with OBD, White

Standard Lead Time:

• 4 Weeks Plus Transit Time

OPTION #2:

Tuttle & Bailey Air Distribution consisting of:

- (27) pcs of 24 x 24 Lay-In to Round Necks, Model A1100 Plaque Supply Diffuser with Insulated Blanket, White
- (20) pcs of Round Dampers for Model A1100
- (02) pcs of 12 x 12 Lay-In to Round Necks, Model A1100 Plaque Supply Diffuser, White
- (27) pcs of 24 x 24 to 22 x 22 Square Necks, Model A70D Louvered Fixed Blades Ceiling Return Grille, White
- (06) pcs of 24 x 24 to 19 x 19 Model A70DFB Louvered Fixed Blades Ceiling Return Grille with Filter Frame, White
- (04) pcs of 8 x 8 Model CRE500, Egg-crate Return Grille with OBD, White

Standard Lead Time:

• 4 Weeks Plus Transit Time

Note:

- ADD \$ 22.00 For Each Aluminum Plaster Frame If You Need.
- ADD \$ 15.00 For Each Square to Round Adapter if you Need



6175 NW 167th Street – Unit G13 Miami Lakes, FL 33015 305-362-4320 Office / 305-362-4502 Fax www.precisionventilation.com

United Enertech consisting of:

(01) pc of 48" w x 14" h of Model DCFL-D-6, Miami Dade County Louvers, 6" Deep Drainable Horizontal Blades with Flange, Kynar 500 Non-Metallic Finish (U.E.'s Standard Color Chart)

(33) pcs of Assorted Sizes Manual Control Dampers, Aluminum Construction with Side Plate and Hand Quad Operator. (01) pc of 48" w x 14" h of Low Leakage Motorized Control Dampers, 316 Stainless Steel Construction, 120 Volt Actuator with Side Plate.

(09) pcs of Assorted Sizes of Model FDD-B Fire Dampers Type B, Dynamic Type, 16" Long - 20 Gauge Sleeve, (2) Sets of Angles.

Standard Lead Time:◆ 4 Weeks Plus Transit Time		
Total Price	.\$ 4,605.00 Plus Sales Tax, Full	Freight Allowed to South Florida
(01) pc of GREENHECK of 300 CFM @.375 SP Mod Centrifugal, Direct Drive Roof Exhaust Fan, 115/60/6 S/S Back Draft Damper, 304 S/S Bird Screen, 18" His	60, VG Motor Disconnect Switch,	
Standard Lead Time:		
Total Price	\$ 1,290.00 Plus Sales Tax, Full	Freight Allowed to South Florida
 (Y) This Quotation Is Based On The Email Take Off Engineer Revision If Items Are Not Listed, They Are Not Included. V (Y) All Items Are Custom Per Job Specifications & It (N) Submittals Were Provided With This Quotation F 	Ve Ask That You Check Our Quality Is Non-Cancellable If Released	uote For Accuracy.
This Quotation Is Being Accepted For Ordering:		
Submitted By, Alina Lopez	Signature	Date