



D&N DUCT SOLUTIONS, INC.
3128 W 81st Street
Hialeah, FL. 33018
Ph: 305-749-5686 Fax: 305-928-1058
dnduct.com

PROPOSAL

Customer: Integ
Job: GG Driver Lounge Building
Plans: N/A
Plans Revision Date: N/A
Date: 9/9/2020

Contract Agreement

This quote is solely based on the fabrication of sheet metal ductwork in accordance with the project plans provided by the customer. Any revision to the project plans will require a new quote. Additional ductwork that is not in the scope of the project's plans will lead to additional charges. Any differences between the included specifics on this proposal and project's scope will require a new quote. The quote provided in this proposal excludes tax. This quote includes delivery of ductwork to the project's site and accessory items for the project such as hangers, slips and drives, cleats, gasket tape, bolts, and screws.

Specifications

Includes:

- Sheet metal ductwork shall be fabricated in compliance with the latest SMACNA Construction Standards.
- Ductwork will be assembled otherwise unassembled per customer request.
- Ductwork will be fabricated using the following pressure classes:
 - **Rectangular ductwork was quoted using 2" W.G.**
- Each piece of ductwork will have a unique label detailing its measurement and zone where it belongs.
- Plastic wrapping of ductwork if requested.
- **Rectangular ductwork was quoted as single wall bare metal.**
- **Rectangular manual volume dampers up to 12".**
- Ductwork will have Pittsburgh Lockseam.
- Ductwork will have a corresponding TDX, Slip and Drive, Flanged, or Raw connection.
- 90 degrees elbow will be fabricated using 2" double wall type turning vane.

Does Not Include

- **Installation of ductwork.**
- Any paint or antimicrobial coating of the ductwork.
- **Round ductwork.**
- **Shoe-taps connecting to flexible ductwork.**
- **Any existing ductwork or demolition of ductwork.**
- **Miscellaneous items such as line jacks, roof curb, frames, angles, stands, wire mesh.**

Total Price.....\$1,350.00 + TAX

This quote is valid for 60 days due to material pricing changes.